



WINGFIELD TRANSPORT TERMINAL

Bardavcol's role was to design and construct an expansion to the Transport Terminal it had previously constructed in 1997.

Key features include:

- Office and fire wall between office and warehouse was constructed of concrete tiltwall panels.
- Warehouse construction consisted of concrete floors steel portal frame with metal cladding to roof and walls.
- External pavements were extra heavy duty to handle container forks, this consisted of cement treated quarry products and finished with a 100mm hotmix.
- Additional warehousing, new coolroom, new fire services, air-conditioning, new loading dock and dock levellers, external heavy duty pavements and set down areas, stormwater drainage and landscaping, security services & fencing.

Client:

National Property Investment

Project Value:

\$3.1 Million

Project Program:

Commenced

May 2002

Completed by

December 2002